

# TENDER NOTICE



## DAV PUBLIC SCHOOL

POWERGRID CAMPUS, BIHARSHARIF, NALANDA

(MANAGED BY DAV COLLEGE MANAGING COMMITTEE, NEW DELHI)

DAV Public School, Powergrid Campus, Biharsharif, Nalanda invites sealed Tenders (Technical & Financial bid separately) on item rate basis on behalf of DAV CMC, New Delhi for **Renovation of Ground Floor of Old Block of School Building (Flooring & Wall Tiles of Corridor and Lobby)** as per estimate of architect at DAV Public School, Powergrid Campus, Biharsharif, Nalanda. Interested well experienced & Govt. Registered Tenderers/ bidders may visit our official website: <http://www.davbiharsharif.co.in> for details of the tenders & B.O.Q and also advised to visit schools office between 09.00 a.m to 02.00 p.m on every working day to verify the site. Last date for submission of tender is 08.08.2024.

**For further queries please contact – 9934431959**

**Principal**

**DAV PUBLIC SCHOOL**  
Powergrid Camus

**Manager**

**DAV PUBLIC SCHOOL**  
Powergrid Camus

**Asstt. Regional Officer**

**Bihar Zone-E, Gaya**

# **ADVERTISEMENT FOR TENDER**

**Ref.no:DAV/PGC/BSF/NLD/Building/2024-25/ Date:03/08/2024**

DAV Public School, Powergrid Campus, Biharsharif, Nalanda, Bihar on behalf of DAV CMC, New Delhi invites sealed tenders from interested eligible construction companies for renovation work at DAV Public School, Powergrid Campus, Biharsharif, Nalanda, Bihar such as **Renovation of Ground Floor of Old Block of School Building (Flooring & Wall Tiles of Corridor and Lobby)** as per the estimate of architect and approved by DAV College Managing Committee, New Delhi against the terms & conditions mentioned below:-

1. The lowest quoted rate/tender will be selected by the competent authority / Building sub- committee.
2. Offered rates are negotiable.
3. Standard quality materials be used.
4. The Work must be completed within 15 days from the date of allotment of the said work.
5. Sealed quotations be sent to the Principal, DAV Public School, Powergrid Campus, Biharsharif, Nalanda, Bihar, Pin Code- 803216.
6. Specifications provided by the Architect should be studied properly before submitting the bid (technical bid / financial bid).
7. The details of the work to be done is available in the school's website i.e [www.davbiharsharif.co.in](http://www.davbiharsharif.co.in).
8. Interested parties are requested to visit DAV Public School, Powergrid Campus, Biharsharif, Nalanda, Bihar site if they wish, before quoting the rates.
9. Technical bid should be submitted on or before 08.08.2024 through email at [davpowergrid@gmail.com](mailto:davpowergrid@gmail.com)
10. Information regarding selection and rejection of technical bid will be intimated through mail.
11. Last date for submitting the sealed financial bid (By post or by Hand) will be 08.08.2024. After that no entry will be accepted.
12. The financial bid will be opened on 10.08.2024 at Regional Office, DAV Public Schools, Bihar Zone-E, C/o DAV Public School, Cantt Area, Gaya, Bihar at 11:00 a.m.
13. The competent authority / Building Sub-Committee reserves the right to accept or reject any of the tenders without assigning any reason.
14. All payments by the employer under the contract/ agreement will be made by mutual understanding on submission of running bill and has to be approved by the designated Architect.
15. The defect and liability period shall be for 12 months. 10% of final approved bill amount of the contractors shall be retained as retention money upto 12 months from the date of handing over.

**Principal**

**Asstt. Regional Officer cum Manager**

**FOR TECHNICAL APPROVAL**

<b>ABSTRACT OF COST OF RENOVATION OF FLOORING &amp; WALL TILES OF CORRIDOR &amp; LOBBY OF OLD BLOCK AT GROUND FLOOR OF D.A.V. PUBLIC SCHOOL, POWER GRID CAMPUS, BIHAR SHARIF, NALANDA, BIHAR.</b>						
<b>Sl.No.</b>	<b>S.O.R.</b>	<b>DESCRIPTION</b>	<b>Qty.</b>	<b>Unit.</b>		
<b>(1) RENOVATION OF FLOORING &amp; WALL TILES OF CORRIDOR &amp; LOBBY</b>						
Area of Flooring = 2351.67 Sft (218.56 Sqm); Area of wall tiles = 1490.52 Sft(138.52 Sqm)						
<b>SECTION - I (DISMANTLING WORK)</b>						
1	15.2	Demolishing cement concrete including disposal of material within 50 metre lead:				
	15.2.1	1:3:6 or rich mix	16.66	Cum		
2	15.56	Dismantling old plaster or skirting racking out joints and clearing the surface for plastering including disposal of rubbish to the dumping ground within 50 metres lead.	138.52	Sqm		
3	15.60	Disposal of building rubbish/ malba/ similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved.	18.35	Cum		
<b>SECTION-II (R.C.C./P.C.C. WORK)</b>						
4	4.1	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work upto plinth level.				
	4.1.3	1:2:4 (1 cement, 2 coarse sand, 4 graded stone aggregate 20mm nominal size.)	16.66	Cum		
<b>SECTION - III (FLOORING WORK)</b>						
5	11.36	Providing and fixing first quality ceramic glazed wall tiles confirming to IS 15622(Thickness to be specified by manufacturer) of approved make in all colours, shades except burgundy, bottle green, black of any size as approved by engineer in charge in skirting, risers of steps and dados over 12mm thick bed of cement mortar 1:3 (1 cement, 3 coarse sand) and jointed with grey cement slurry @ 3.3 Kg/sqm including pointing in white cement mixed with pigment of matching shade complete.	138.52	Sqm		
6	11.41A	Providing and laying vitrified tiles in floor in different sizes (thickness to be specified by the manufacturer) with water absorption's less than 0.08% and confirm-				

Sl.No.	S.O.R.	DESCRIPTION	Qty.	Unit.	Rate	Amount
		ing to IS: 15622 of approved brand & manufacturer, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement: 4 coarse sand) jointing with grey cement slurry & 3.3 kg/sqm including grouting the joints with white cement and matching pigments etc. The tiles must be cut with the zero chipping diamond cutter only. Laying of tiles will be done with the notch trowel, plier, wedge, clips of required thickness, leveling system and rubber mallet for placing the tiles gently and easily.				
	11.41A.3	Glazed Vitrified tiles Matt/Antiskid finish of size 11.41A.3.1- Size of Tiles 600x600 mm	218.56	Sqm		
7	11.72	Providing designation 100A one brick flat soling joints filled with local sand including cost of watering, taxes, royalty all complete as per building specification ad direction of E/l.	218.56	Sqm		